

Date: Thursday, 3/9/2006 8:36:03 AM
 User: Linda Lacelle

Process Sheet

Customer :	CU-DAR001 Dart Helicopters Services	Drawing Name :	INLET ADAPTER
Job Number :	26180		
Estimate Number :	12160		
P.O. Number :	N/A	Part Number :	D3479041
This Issue :	3/9/2006	S.O. No. :	N/A
Prsht Rev. :	NC	Drawing Number :	D3479 REV A
First Issue :	N/A	Project Number :	N/A
Previous Run :	N/A	Drawing Revision :	A
	Type :	Material :	N/A
	SMALL / MED FAB	Due Date :	3/30/2006
Written By :	<i>SEE COMMENT BELOW</i>		Qty: 2 Um: Each
Checked & Approved By :	<i>SEE ABOVE USER & DATE</i>		
Comment :	Est Rev: A New Issue 06-02-02 JLM		

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	D34791	TUBE
-----	--------	------



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Pick:

Qty	Part Number	Description	Batch
1	D3479-1	Tube	<i>26288</i>

Bob 03-29 (2)

2.0	D34795	FLANGE PLATE
-----	--------	--------------



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Pick:

Qty	Part Number	Description	Batch
1	D3479-5	Flange	<i>26288 26133</i>

Bob 03-29 (2)

3.0	D34793	TAB
-----	--------	-----



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Pick:

Qty	Part Number	Description	Batch
1	D3479-3	Tab	<i>26290</i>

Bob 03-29 (2)

4.0	D34797	TAB
-----	--------	-----



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Pick:

Qty	Part Number	Description	Batch
1	D3479-7	Tab	<i>26291</i>

Bob 03-29 (2)

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☒ No ☐ DQA: ☒ Date: 26/03/13

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Thursday, 3/9/2006 8:36:03 AM
User: Linda Lacelle

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: INLET ADAPTER

Job Number: 26180

Part Number: D3479041

Job Number:



Seq. #: Machine Or Operation: Description :

5.0 SMALL FAB 1

SMALL & MEDIUM FAB RESOURCE 1



Comment: SMALL & MEDIUM FAB RESOURCE 1

1-Assemble as per Dwg D3479

2-Spot Weld as per Dwg D3479 and Dart QSI 018

VB 06.03.29 (2)

6.0

QC5/9

WELD INSPECTION



Comment: WELD INSPECTION

06.03.29 (2)

7.0

OUTSIDE SERVICE

OUTSIDE SERVICES



Comment: Sub-Contracting OUTSIDE SERVICES

Issue P/O: _____

Electro Chemically Polish weldment as per Dwg D3476

Ensure Certificate of Conformity is attached

8.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Receive & Inspect for Transit Damage

Ensure Material Release Note is attached

9.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

10.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: _____

06.03.29 (2)

11.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

06.03.30 (2)

Job Completion



U 06.03.30

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____






QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

PRELIMINARY ISSUE

DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D3479	REV. A SHEET 1 OF 4
DATE 06.01.18		TITLE INLET ADAPTER	SCALE 1:2
A	06.01.18	NEW ISSUE	



DETAIL B: SPOT WELDING TABS
D3479-3/-7
SCALE 1:1



D3479-041 INLET ADAPTER

NOTES:


- 1) SPOT WELD PER DART QSI 018
- 2) FINISH: ELECTRO CHEMICALLY POLISH
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.010

PRELIMINARY ISSUE

DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D3479	REV. A SHEET 2 OF 4
DATE 06.01.19	TITLE INLET ADAPTER		SCALE 1:2



D3479-1 TUBE




D3479-1F FLAT PATTERN

8.7


NOTES:

- 1) MATERIAL: AISI 304/316 SS SHEET PER MIL-S-5019 (ANNEALED) 2B FINISH
26 GAUGE SS (0.018 THICK)
(REF. DART SPEC. M304S26GA)
- 2) SPOT WELD PER DART QSI 018
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.010





PRELIMINARY ISSUE

DESIGN [Signature]	DRAWN BY [Signature]	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D3479	REV. A SHEET 3 OF 4
DATE 06.01.19		TITLE ADAPTER INLET	SCALE 2:1





D3479-3F FLAT PATTERN

- 1) MATERIAL: AISI 304/316 SS SHEET PER MIL-S-5019 (ANNEALED) 2B FINISH
26 GAUGE SS (0.018 THICK)
(REF. DART SPEC. M304S26GA)



D3479-3 99 DEGREE TAB (MAKE FROM D3479-3F FLAT PATTERN)






D3479-7 81 DEGREE TAB (MAKE FROM D3479-3F FLAT PATTERN)

NOTES:

- 2) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 3) ALL DIMENSIONS ARE IN INCHES
- 4) BREAK ALL SHARP EDGES 0.005 TO 0.010

PRELIMINARY ISSUE

DESIGN 	DRAWN BY 	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D3479	REV. A SHEET 4 OF 4
DATE 06.01.19		TITLE ADAPTER INLET	SCALE 1:1



D3479-5 FLANGE PLATE

NOTES:

- 1) MATERIAL: AISI 304/316 SS SHEET PER MIL-S-5019 (ANNEALED) 2B FINISH
26 GAUGE SS (0.018 THICK)
(REF. DART SPEC. M304S26GA)
- 2) PART IS SYMETRICAL ABOUT CENTERLINE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.010

COPYRIGHT © 2006 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.